



# LEGALETT<sup>®</sup>

## WORLDWIDE

Sweden | Canada | USA | Finland | Germany | Japan | Lithuania | Norway | Poland


# Understanding The Plans

LEGALETT engineered plans are job specific

Each detail, cross section and note has a purpose so don't take short cuts.







One or more reviews of the drawings is recommended before jobsite start up

# GEO-Slab Installation Manual








# A Full Set Of Plans Is Provided

Details, material lists and easy installation tips specific to each project make for a seamless installation



# A Full Set Of Plans Is Provided

Installation is broken down into easy steps specific to each project



# General Notes

- **General Notes are included in the drawing, which provide important project information.\*\***

GENERAL NOTES

GENERAL NOTES: STRUCTURAL GEO-SLABS

GENERAL NOTES: LEGALETT HEATED GEO-SLABS

- **\*\*** BUILDING HEAT LOSS AND TOTAL BUILDING HEATING SYSTEM DESIGN BY OTHERS.  
VENTILATION AIR MUST BE HEATED TO INDOOR AMBIENT TEMPERATURE BY OTHERS.  
HEAT REQUIRED FOR INFILTRATION BY OTHERS.

# Materials List

- **A Bill of Materials is included in the drawing, which outlines all the items that will be shipped with your order.**

| 0302 8" SLAB LEGALETT SUPPLIED MATERIALS XXXX SAMPLE PROJECT |   |              |                    |                        |
|--|---|--------------|--------------------|------------------------|
| #  | ITEM  | QTY          | PRODUCT DATA SHEET | REMARKS                |
| 7843   | 5500W FAN, EXCHANGERS, FAN FRAME                        | 2 PC(S).     | 0550               |                        |
| 7842   | 5500E FAN, ELEMENTS, FAN FRAME                          | 0 PC(S).     | 0551               |                        |
| 7058   | 5000 SHEET METAL BOX, 4"                                | 2 PC(S).     | 0552               |                        |
| 7087   | 24V 3-WIRE DIGITAL PROGRAMMABLE THERMOSTAT (BWR)        | 4 PC(S).     | 0513               |                        |
| 7108   | 90° PVC ELBOW   | 109 PC(S).   | 0508               | 4 EXTRA                |
| 7109   | 45° PVC ELBOW   | 38 PC(S).    | 0508               | 4 EXTRA                |
| 7111   | 45° PVC FITTING ELBOW                                   | 24 PC(S).    | 0508               |                        |
| 7018   | 4" GALVANIZED STEEL CAP                                 | 8 PC(S).     | 0508               |                        |
| 7107   | 4" PVC LEGALETT RED PIPE                                | 97 PC(S).    | 0508               |                        |
| 7095   | 30mm (1") CONTINUOUS CHAIRS FOR 6" & 8" SLABS           | 250 PC(S).   | 0514               |                        |
| 7079   | 40/50mm (2") CHAIRS FOR 4" UNHEATED PORCHES             | 0 PC(S).     | 0514               |                        |
| 7094   | 70mm (3") CONTINUOUS CHAIRS FOR 5" UNHEATED SLABS       | 0 PC(S).     | 0514               |                        |
| 7090   | 100mm (4") CONTINUOUS CHAIRS FOR 8" UNHEATED SLABS      | 0 PC(S).     | 0514               |                        |
| 7091   | 150mm (6") CONTINUOUS CHAIRS FOR 11" UNHEATED SLABS     | 18 PC(S).    | 0514               |                        |
| 7063   | JOBSITE SIGN  | 1 PC(S).     | 0501               |                        |
| 7030   | NEW CONSTRUCTION HEATER                                 | 0 PC(S).     | 0509               |                        |
| 7106   | NEW CONSTRUCTION HEATER BOX                             | 0 PC(S).     | 0509               |                        |
| 7057   | CONSTRUCTION HEATER ADAPTER FOR 3000 SERIES HEATER      | 0 PC(S).     | 0509               |                        |
| 1152   | 14" EDGE ELEMENTS FOR 8" SLAB, 3" EPS, L-SHAPE          | 31 PC(S).    | 0507               | 9503 - 9 PC(S) COPED   |
| 1156   | 12" EDGE ELEMENTS FOR 6" SLAB, 2" EPS, L-SHAPE          | 0 PC(S).     | 0507               | 9503 - 0 PC(S) COPED   |
| 1164   | 11" EDGE ELEMENTS FOR 5" SLAB, 3" EPS, L-SHAPE          | 0 PC(S).     | 0507               | 9503 - 0 PC(S) COPED   |
| 8013   | 2-9/16" x 1-1/8" STEEL CAP                              | 27 PC(S).    | 0507               |                        |
| 1188   | 5000 SHEET METAL BOX FOAM SHIM FOR 8" SLAB, 3" THK.     | 2 PC(S).     | 0530               |                        |
| 9000   | EXPANDED POLYSTYRENE INSULATION SHEET 4'x8'x3", TYPE II | 119 PC(S).   | 0514               | 3 EXTRA                |
| 9001   | EXPANDED POLYSTYRENE INSULATION SHEET 4'x8'x2", TYPE II | 0 PC(S).     | 0514               |                        |
| 1172   | MESHED SIDE SKIRTING - EPS 2'x8'x2", TYPE II            | 0 PC(S).     | 0537               |                        |
| 1174   | MESHED SIDE SKIRTING - EPS 4'x8'x3", TYPE II            | 8 PC(S).     | 0537               | 1 EXTRA                |
| 1173   | MESHED CORNER SKIRTING SET - EPS 2'x8'x2", TYPE II      | 4 PC(S).     | 0537               |                        |
| 1153   | CANADIAN PIPE SUPPORTS, 4" PIPE, 1" SADDLE              | 297 PC(S).   | 0508               |                        |
| 1166   | 4"x4"x3" 80mm CHAIR SPACER (BLOCK)                      | 0 PC(S).     | 0514               |                        |
| 1169   | 4"x8"x2" THICKENED EDGE SPACER (BRICK)                  | 0 PC(S).     | 0514               |                        |
| 8009   | REBAR TIES  | 550 PC(S).   | 0514               |                        |
| 8012   | SHEET METAL SCREWS                                      | 1,050 PC(S). | 0508               |                        |
| 8016   | 21" TY-RAP, 0.19" WIDTH                                 | 100 PC(S).   | 0538               |                        |
| 1160   | EPS PIPE INSULATION, 4", 60% WRAP                       | 216 FEET     | 0514               | 1,872 SQ.FT. HEATED    |
| 1168   | EPS PIPE INSULATION, 4", 40% WRAP                       | 128 FEET     | 0514               | 178 SQ.FT. UNH. GARAGE |
| 9500   | TOTAL SLAB SQUARE FOOTAGE                               | 2,050 SQ.FT. | 0511               | 0 SQ.FT. PORCH         |


# Reinforcing Schedule/Concrete Volumes

- Concrete volumes and a reinforcing steel schedule is also provided.


| REINFORCING SCHEDULE/CONCRETE VOLUMES  |   |      |        |                        |                              | (SUPPLIED BY INSTALLER<br>OR DISTRIBUTION CENTER) |
|--|---|------|--------|------------------------|------------------------------|---|
| NO ADJUSTMENT FOR CONCRETE PUMP OR PIPING VOLUME. PIPE VOLUME IS 2.4 m <sup>3</sup> / 3.1 YDS. |   |      |        |                        |                              |   |
| MARK   | NO. BARS  | SIZE | LENGTH | DESCRIPTION            | REMARKS                      |   |
| 106000   | 16  | #4   | 20'    | CUT INTO 10'-0" PIECES | EDGE LOADS                   |   |
|  |   |      |        |                        |                              |   |
|  |   |      |        |                        |                              |   |
| WWF  | 26 SH. 152 X 152 / MW18.7 X MW18.7 IN 8' X 20' FLAT SHEETS                                  |      |        |                        | 6X6, 6 GAUGE                 |   |
| 25 CONC.   | 0 m <sup>3</sup> / 0 YDS. 25 MPa/3500 PSI, 3/4" AGGREGATE, NO AIR, NO CHLORIDE ADDITIVES    |      |        |                        | INTERIOR SLABS               |   |
| 32 CONC.   | 34.0 m <sup>3</sup> / 44.5 YDS. 32 MPa/4500 PSI, 3/4" AGGREGATE, AIR, NO CHLORIDE ADDITIVES |      |        |                        | EXPOSED SLABS (INCL. GARAGE) |   |



# Structural Details



# Some Of The Tools You Will Need



# Materials You Will Need

## ■ **Materials - Suggested**

- 1. rebar stakes and string line
- 2. Wire mesh and rebar as per drawing
- 3. Rebar Dowels (ICF walls)
- 4. Rigid or flexible 1" electrical conduit, complete with fittings, locknuts and PVC cement to sleeve water lines
- 5. ½" or ¾" oxygen barrier PEX for water lines (cut ends at 45° for ease of installation in sleeves)
- 6. Wire pulling lubricant and or pull string for long water line runs
- 7. Patio stone or cinder block or large stone to weigh down furnace box

# Tools You Will Need

- **Tools - Suggested**
- 1. Auto leveling laser with receiver - 2nd receiver helpful for larger slabs
- 2. Saws - handsaw, keyhole/pruning saw, miter saw, battery reciprocating saw with long blade and circular saw
- Leaf blower
- 3. Utility knife, extendable blade recommended such as H-1 Olfa
- 4. Battery drills with magnetic 1/4" hex drivers and #2 (red) Robertson
- 5. Tape measures
- 6. Chalk line with red chalk
- 7. Drywall T-square
- 8. Framing Square
- 9. Magic markers, pencils
- 10. Hammers – claw, small sledge and rubber mallet

# Tools You Will Need

- 12. Bolt cutter
- 13. Shovel and wheelbarrow
- 14. Landscaping rake (36" wide) and comb rake
- 15. Rebar tie spinners
- 16. Generator if power not available (including gas, oil)
- 17. Extension cords
- 18. Flood lights if required for night work
- 19. Small (18") plate packer or small vibrating roller
- 20. Hearing, eye, hand, foot and head protection
- 21. Architectural drawings for building to verify dimensions, possible interferences (floor drains, plumbing etc.), conduit locations and verify heater box locations are in appropriate locations
- 22. Scale ruler - 1:100 and 1:50 (or 1:25 depending on plan scale)
- 23. Provide for waste disposal
- 24. Low Expansion foam gun and foam canisters

# Insulated Formwork

- **Wire cut EPS billets contain the edge elements, insulated pipe caps and pipe support chairs.**




Legalet GEO-Slab

---

Site Work

# What Are Organics

- Organics are black soil layers (O and A) that contain leaves and plant matter that can decompose and settle
- Minor roots are acceptable (B)





# Establish Building Footprint

- **Set up string lines 3-4 ft. outside of the building footprint to allow for excavation**
- **Remove surface soils to correct elevation to allow for the overall depth of Legalett assembly.**



# Site Preparation

- **Place sufficient clear stone for easy trenching of under slab services 6"+ \*\* more stone allows for easier trenching of utilities**



\*\*Refer to Excavation and Skirting Product Data Sheet to determine excavation depth.

# Excavate With Drainage to Daylight

- **Ensure gravity drainage to daylight**

**\*\* Do not create a swimming pool effect \*\***



# Raising The Grade

- Build up grade with compacted fill only if required.
- This can be pit run, sand, “A” or “B” gravel or 3” “breaker run”.
- Fill must be compacted in 6”- 12” lifts.
- (3” breaker run shown)



# Drainage Layer

- **Build up over sub base with  $\frac{3}{4}$  clear stone and level with a Bob Cat or dozer.**
- **Extend stone 2 feet outside of building footprint**
- **( $\frac{3}{4}$ " clear stone shown)**



# Place and Level Stone

- A dozer with a self levelling blade can be used on larger projects



# A Stone Slinger Makes it Easy

- Alternately a Stone Slinger can also be used to place the stone.



# Leveling with 3/8" (10 mm) stone

(OPTIONAL)

- Place 1" – 2" of pea gravel (3/8" clear stone) on top of the 3/4" stone to make final leveling easier
- Level to +/- 1/4" around the perimeter and to within 1/2" everywhere else using a small vibrating plate packer.
- If 3/8" stone is not used, level 3/4" stone as above.





# Plumbing and Services

- **Locate and place plumbing risers and all other slab services.**
- **- Water, Electric, Gas, etc..**
- **\*\* Clear stone placed in trenches for main lines prior to stone going down will make it easier to dig later.**



# Final Leveling

- Re-level after plumber to within  $\frac{1}{4}$ " of desired elevation under edge elements and within  $\frac{1}{2}$ " everywhere else.
- Compaction is not required again.



# Slab Penetrations

- **All services must be in place before the insulation is installed.**



# Check List For Delivery

Have an area large enough for a tractor trailer to back into ready  
Also an area large enough to place all the materials

Minimum of 4 able bodied people onsite to unload the truck will be needed

Note: 1 hour unload time is provided. Longer unload times may be back charged  
Wear safety protective gear including gloves and safety boots.



# Delivery of Materials

- All materials including heating pipes and fittings, protected skirting, insulated form work, and snake chairs to support wire reinforcing are shipped to site



# EPS Blocks

- **Wire cut EPS billets contain the edge elements and insulated pipe caps.**
- **Pipe support chairs will be in a separate box.**




# Installing EPS Form Work

---



# Step 1

## Base Foam Layout



Cut off piece used to start returning rows


Start by laying out 4 x 8 sheets of EPS around the perimeter



# Begin By Placing EPS Base Layer

---


- Place EPS base layer as per layout provided 2” beyond the perimeter edge of the building. Use the dimensions provided by Legalett for this.



# Chalk Lines as per Legalett Dimensions




# Step 2 Edge Element Layout




# Step 2 Edge Element Layout

There will be 4 unused female copes that will need to be cut off so the remaining straight edge elements can be used



Short jogs in the wall that require back to back male and female copes will require the straight parts of the male and female copes to be trimmed to length



# Place Pre-Cut Corners

- All 90-degree corners come already coped.
- All other angles will need to be cut on site.



# Place Edge Elements




# Form Support with 6" Plastic Nails

- **Locking the Edge elements to the base with EPS foam and the plastic stakes eliminates the need to back fill or use whalers to support the edge during concrete placement.**



# Finished Corner


- Lock the corners together by screwing through overlapped metal cap provided.





# Staggered Joints

- **Stagger the joints of the metal caps with those of the edge elements.**



# ThermaSill PH

ThermaSill PH provides a minimum R14 at thresholds and can be sized to fit any wall thickness or R value requirements.


Made from EPS and NEXCEM it can be screwed into, supports loads, is fire rated.



“Exclusively from Legalett “

# ThermaSill PH

- **Insert  
ThermaSill  
PH as per  
location on  
Legaletts  
supplied  
plans**




# ThermaSill PH

- **Bend up one edge of the metal track and screw through the metal to hold ThermaSill PH in place**



# Heater Box Bottom Drain Shim

- Place foam drain shim in area below heater box




\* If using Stego membrane, puncture the membrane at the drain hole locations






# Step 1

## Porches and Skirting

Add porches and skirting as shown




**LEGEND**

|                         |   |   |
|-------------------------|---|---|
| 4'x8'x5" TYPE II SHEETS | FULL  | PIECE   |
| 4'x8'x3" TYPE II SHEETS |  |  |
| 3" SHEETS + MESH ADDED  |  |  |
|                         |  |   |


Apply Legalett tape at centerline of skirting. Fasten mesh rolls to EPS with supplied tacks

# Corner Skirting

## Right



## Wrong



This pre-cut notch **should have been removed** from the corner edge element. This leaves a space between the skirting and the corner edge element which could allow frost to penetrate. Install prior to pour where practical.


# Install Stego Membrane (when specified)

## NOTE:

Do not proceed to Step 3 until Stego membrane has been installed



Stego outline in yellow is sandwiched between the 2 layers of EPS





# Installing Stego Membrane




Roll out membrane 6" past the edge element and tape all seams with Stego tape (supplied by Legalett)



# Temporary Drain\* For Stego


- During assembly leave a 2' x 2' area and drill a 3" hole in the center of it every 1000 sq.ft. to allow water to drain
- \* Note: This is only required if a membrane is being used



# Temporary Drain Covered


Before concrete placement patch over filled drain hole and patch and seal seams with Stego seaming tape and install top layer of EPS

Cover hole in mesh with 1 layer of 3' x 3' mesh




Fill temporary drain hole with low expansion foam

# Step 3 Top Infill Foam Layout



# Install Rigid Conduit Sleeves


Do not proceed to step 4 until Rigid conduit for water lines and boiler interlock have been installed and the 48' x 48" cut out has been done.








# Step 4

## Install Heater Distribution Box

The heater distribution box must be oriented as per the drawings supplied.




**IMPORTANT NOTICE – ALWAYS INSTALL CONDUITS BEFORE AIR PIPING**

| 10' FLEXIBLE CONDUIT                   | PC. # | SLEEVES USED FOR  | CONNECTS TO                                     | NOTES  |
|--|-------|---|---|--|
| 3/4" FLEX CONDUIT<br>CUT INTO 3 PIECES | 1     |  INSERT POWER  | POWER RECEPTACLE BOX ON HEATER                  | URNS UP INTO ADJACENT WALL   |
|  | 2     |  THERMOSTAT WIRING   | THERMOSTAT WIRE INLET ON HEATER BOX             | URNS UP INTO ADJACENT WALL   |
|  | 3     |  BOILER INTERLOCK WIRING   | BOILER INTERLOCK WIRE INLET ON HEATER BOX       | RUNS TO BOILER ROOM THROUGH RIGID CONDUIT UNDER CONCRETE THROUGH CHANNEL CUT INTO TOP LAYER OF EPS |
| 1" FLEX CONDUIT<br>CUT INTO 2 PIECES   | 1 & 2 |  OXYGEN BARRIER<br> PEX | WATER SUPPLY AND RETURN LOCATIONS ON HEATER BOX | RUNS TO BOILER ROOM THROUGH RIGID CONDUIT UNDER CONCRETE THROUGH CHANNEL CUT INTO TOP LAYER OF EPS |

\*REFER TO 208B FOR HEATER BOX LOCATION (PLACE HEATER BOX DIRECTLY ON SHIM)\*

# 5000 series Heater Box



# 5000 series Heater Box






# Installing Bottom Mesh






# Step 5


## Bottom Mesh Layout



# Place Snake and Plastic Chairs

## LEGEND


|                       |  |
|-----------------------|--|
| 1" SNAKE CHAIRS       |  |
| 3" SNAKE CHAIRS       |  |
| 1-1/2" PLASTIC CHAIRS |  |



# Base Layer Perimeter Reinforcement

Bottom mesh sits on 1 row of snake chairs and 1 row of plastic chairs where it is over top of the Stego Membrane

Do not overlap the mesh




# Bearing Wall Reinforcement

- **Install reinforcement under any bearing walls with supplied chairs, as per design provided.**




# Point Load Reinforcement



**Install reinforcement under any point loads as per drawings provided.**

# Point Load Reinforcement

**Higher loads up to 100,000lbs can be designed for by increasing concrete thickness and amount of reinforcing in those areas.**





# Installing The Heating System






# Step 6

## Pipe Layout







Thermostats are located




Elbow Qty per loop is shown

### PIPING LEGEND

-  AIR PIPE FULLY INSULATED.
-  AIR PIPE WITH TOP HALF INSULATED.
-  AIR PIPE WITH NO INSULATION.
-  SUGGESTED THERMOSTAT LOCATION

# Pipe Insulation Layout

- The shop drawings will indicate where pipe insulation is required.
- Refer to the legend for where full insulation is needed or half insulation is needed.



# Pipe Summary Number Of Loops

A Pipe Cut List accompanies every project.

The cover page summarizes the runs

LEGALETT.

4" Pipe Cut List Page 1 of 9

Legalet Project # 16059

|                     |                |               |             |
|---------------------|----------------|---------------|-------------|
| Order Date          | April 13, 2020 | Project Title | Chris Roche |
| Mat'l Delivery Date | May            | City          | Concord, NH |
| Service Rep.        | Ken Williams   | Revision      | Rev. 1      |
| Installer           | Chris Roche    | Prepared by   | Chkd. by    |

Heater 1 Note: 9 heaters max., and entry is 1, 4 or 7 for 4", and 1-9 for 2" Assembly

| Loop | Name | Full Pipe | 90's | 45's |
|------|------|-----------|------|------|
| 1    | 1A   | 11.0      | 10   | 4    |
| 2    | 1B   | 8.2       | 14   | 4    |
| 3    | 1C   | 9.6       | 12   | 4    |
| 4    | 1D   | 9.8       | 14   | 0    |
| 5    | 1E   | 10.4      | 12   | 2    |
| 6    | 1F   | 11.6      | 8    | 6    |
| 7    | 1G   | 9.6       | 12   | 4    |
| 8    | 1H   | 11.8      | 9    | 4    |

Assembly

Cut By

Assembled By

Checked By

Heater 2

|    |    |     |   |   |
|----|----|-----|---|---|
| 9  | 2A | 0.0 | 0 | 0 |
| 10 | 2B | 0.0 | 0 | 0 |
| 11 | 2C | 0.0 | 0 | 0 |
| 12 | 2D | 0.0 | 0 | 0 |
| 13 | 2E | 0.0 | 0 | 0 |
| 14 | 2F | 0.0 | 0 | 0 |
| 15 | 2G | 0.0 | 0 | 0 |
| 16 | 2H | 0.0 | 0 | 0 |

# Pipe Cut List

There is a pipe cut list for each loop with the individual lengths of each piece and the type of elbow that is needed at each connection

|                     |  |                |  |                                     |  |
|---------------------|--|----------------|--|-------------------------------------|--|
| <b>LEGALETT</b>     |  |                |  | <b>4" Pipe Cut List Page 2 of 9</b> |  |
|                     |  |                |  | <b>Legalett Project #</b>           |  |
|                     |  |                |  | <b>16059</b>                        |  |
| Order Date          |  | April 13, 2020 |  | Project Title                       |  |
| Mat'l Delivery Date |  | May            |  | City                                |  |
| Service Rep.        |  | Ken Williams   |  | Revision                            |  |
| Installer           |  | Chris Roche    |  | Prepared by                         |  |
|                     |  |                |  | Chkd. by                            |  |

| Component | Cut Length |       | Joining Fitting | Cut/ Assembled |
|-----------|------------|-------|-----------------|----------------|
|           | inches     | mm    |                 |                |
| 1         | 56         | 1,416 |                 |                |
| 2         |            |       | 45°             |                |
| 3         | 12         | 308   |                 |                |
| 4         |            |       | 45°             |                |
| 5         | 249        | 6,315 |                 |                |
| 6         |            |       | 90°             |                |
| 7         | 117        | 2,968 |                 |                |
| 8         |            |       | 90°             |                |
| 9         | 5          | 128   |                 |                |
| 10        |            |       | 90°             |                |
| 11        | 13         | 320   |                 |                |
| 12        |            |       | 90°             |                |
| 13        | 75         | 1,898 |                 |                |
| 14        |            |       | 90°             |                |
| 15        | 150        | 3,802 |                 |                |
| 16        |            |       | 90°             |                |
| 17        | 13         | 320   |                 |                |
| 18        |            |       | 90°             |                |
| 19        | 130        | 3,294 |                 |                |
| 20        |            |       | 90°             |                |
| 21        | 17         | 443   |                 |                |
| 22        |            |       | 90°             |                |
| 23        | 142        | 3,599 |                 |                |
| 24        |            |       | 90°             |                |
| 25        | 325        | 8,254 |                 |                |
| 26        |            |       | 45°             |                |
| 27        | 13         | 323   |                 |                |
| 28        |            |       | 45°             |                |
| 29        | 10         | 263   |                 |                |
| 30        |            |       |                 |                |

|                              |  |
|------------------------------|--|
| Assembly                     |  |
| Cut By                       |  |
| Assembled By                 |  |
| Checked Prior to Shipping By |  |

|      |           |
|------|-----------|
| Loop | <b>1A</b> |
| Pipe | 11.0 pcs. |
| 90's | 10        |
| 45's | 4         |

| Initial Cuts |    |         |
|--------------|----|---------|
| inches       | mm | fitting |
|              |    |         |
|              |    |         |

# Plastic Pipe Cutting Station

Set up a work area close to the slab to cut all pipe lengths as per the “Cut List” provided.

Measure cut length from small end of pipe. When remaining bell end pipe is too short hammer it on to next full length with rubber mallet and continue cutting for no waste

Use a very sharp fine tooth (80 tooth) carbide trim blade to prevent burring for plastic pipe.




# Placing Pipe

- Use a rubber mallet to attach elbows and fittings to the pipe.



# Placing Pipe

- Once all the pipe is in place adjust the position of the loops so they match the provided layout.



# Placing 4" Pipe


- Secure elbows and connectors to the pipe with 2 screws
- The use of duct tape or sealant is ***not required.***






# Pipe Support

- The pipe is supported at the perimeter on the wire mesh below
- Foam Cradles in the infield every 3ft and on each side of a corner




# Pipe Support

- Support each side of an elbow,
- Support every 3' along the pipe with foam chairs provided.
- Pipe chairs not required over mesh strips for 4" pipe




# Complete Piping Insulation

- **Place the larger pipe cap on the top and the smaller pipe cap on the bottom of the supply pipes as per drawings, and secure with tie wraps provided.**
- **Use cradle supports where shown on plans**




# Complete Piping Insulation

- **Install pipe insulation over the top (60%) and bottom (40%) of supply pipes as per drawings, and secure with tie wraps provided.**
- **Large caps (60%) go on the top and small caps (40%) on the bottom**



# Top Only Piping Insulation

- Install pipe insulation over the top (60%) of supply pipes as per drawings, and secure with tie wraps provided.
- Large cap (60%) are only used on the top



# Do Not Insulate The Elbows

- **There is no need to insulate over the elbows - only insulate the straight pipe.**
- **Pipe capping provided does not include material for the elbows**




# Seal Off Unused Inlets/Outlets

- **Ensure any unused inlets/outlets on the sheet metal furnace box are sealed off.**



# Slab Penetrations

- **Plumbing for drains can be formed around with a small wood form stop or a solid EPS block out that can be removed or drilled through later for easy access later.**






# Slab Penetration Details

- Detailed instructions are provided for:
- Recessed showers
- Elevator pits
- Sump pits
- Containment pits
- Sewage ejectors
- Radon Gas venting
- Trench drains



# Placing Upper Reinforcing Steel




# Step 7 Continuous Top Mesh Layout

Continuous layer of mesh.

Overlap mesh 150mm (6") (1 square) at all edges and tie with tie wire.

Use cut-offs from Full Sheets to fill in gaps



# Top Reinforcing Mesh

- Install top layer of reinforcing mesh on top of the heating pipe.




# Top Reinforcing Mesh

- **Overlap the mesh sheets by 6" (one square) in all directions and tie with provided metal ties at 2' o.c.**




# Step 8 Top Perimeter Mesh Strip Layout



Do not overlap perimeter edge mesh strips

# Top Perimeter Reinforcing Mesh

- Add 6" x 6" 6/6 mesh all around the perimeter.
- Width can be found on the plans provided and will vary by project



# Perimeter Reinforcing Mesh


- **Tie top and bottom mesh layers together at the perimeter 48" O.C, with supplied plastic tie wraps.**
- **\* This is required to prevent the edges of the mesh from curling up when walking on it during concrete placement.**
- **Tie interior mesh and any rebar together with metal wire ties.**





# Step 9 Top Steel Layout

10m (#4) Bars x 3000 (10'-0") @ 1000 (40")  
O.C.



# Place and Finish Concrete



# Project Specific Training

---

Legalett's engineers provide personalised project specific on-line video training for each sold project.


Call Legalett at (866)299-7567 ext 101 to learn more about why we may be the solution you have been looking for.

Thank you for your time and attention

# Getting Ready To Pour

Seal lid with  
poly and tape

Weigh down lid  
to keep from  
floating



# Pre Pour Checklist



**Legalett Canada Inc.**  
 103 Warner Drive  
 Long Sault, Ontario, K0C 1P0  
 Tel: 866-299-7567  
 Fax: 613-937-0125  
 E-mail: tech@legalett.ca

(Revised 5/24/11)

## SITE INSPECTION PRE-POUR REPORT LEGALETT INC.

|   |                      |                           |                      |
|---|----------------------|---------------------------|----------------------|
| Date of Inspection:                               | <input type="text"/> | Service Rep:              | <input type="text"/> |
| Legalett Project #:                               | <input type="text"/> | Installer:                | <input type="text"/> |
| Project Title:                                    | <input type="text"/> | Scheduled pour date/time: | <input type="text"/> |
| Drawing and Rev. # from which slab was installed: |                      | <input type="text"/>      |                      |

**DO NOT POUR UNLESS YOU HAVE RECEIVED AN AUTHORIZATION CODE**

All pictures as per Photo Location Plan (provided with drawings) submitted electronically with this report  
 - Number of high quality pictures (min 250 KB each in size) submitted with report \_\_\_\_\_

Checked

**PART 1 - Structural (Report to be done at 100% installation completion) - FOR ALL SLABS ON GROUND**

- 1) Site Prep
  - 3/8"-3/4" clear stone used for top 4"-6" (see drawing) of gravel drainage layer (no fines)
- 2) Edge Element (Does not apply for basements)
  - Height of Edge Element above EPS in middle of slab \_\_\_\_\_
  - Height of Edge Element above EPS at edge of slab \_\_\_\_\_
  - Skirting installed (if any) and photographs provided (minimum 2 photos required)
  - Exterior fill completed or gravel or braces up against edge element (braces only allowed for unskirted slabs)
- 3) EPS Under Slab
  - Type (I,II,III,IV etc.) \_\_\_\_\_ Location (edge, mid., etc.) \_\_\_\_\_
  - Type (I,II,III,IV etc.) \_\_\_\_\_ Location (edge, mid., etc.) \_\_\_\_\_
  - Type (I,II,III,IV etc.) \_\_\_\_\_ Location (edge, mid., etc.) \_\_\_\_\_
  - Staggered Joints
- 4) Reinforcement
  - Continuous top wire mesh as per drawing
  - Top and bottom edge strips of wire mesh, tied around pipe with ty-raps, as per drawing
  - Wire mesh chaired as per drawing
  - Wire mesh and/or rebar under all bearing walls and posts as per drawing
  - Top rebar placed and spaced as per drawing
  - Concrete cover to be minimum 20 mm (3/4") for top and 30 mm (1-1/4") for bottom
- 5) Elevation and Drainage
  - Slab elevation allows for adequate drainage, min. 5% slope (6" drop 10' away from slab edge)
  - Gravel drainage layer drains to daylight or sump
- 6) Slab Penetrations by Others
  - Check for any other service or penetration (or bundle of penetrations) greater than 6" in diameter within the perimeter reinforcing - if so explain and provide picture.



**Legalett Canada Inc.**  
 103 Warner Drive  
 Long Sault, Ontario, K0C 1P0  
 Tel: 866-299-7567  
 Fax: 613-937-0125  
 E-mail: tech@legalett.ca

(Revised 5/24/11)

## SITE INSPECTION PRE-POUR REPORT LEGALETT INC.

**DO NOT POUR UNLESS YOU HAVE RECEIVED AN AUTHORIZATION CODE**

**PART 2 - Mechanical (Report to be done at 100% installation completion) - FOR HEATED SLABS ONLY**

- 1) Heating Box (insert not yet received/installed)
  - Type (water or electric) \_\_\_\_\_ Quantity \_\_\_\_\_
  - Location as per plan
  - Check that box orientation matches plan, noting orientation of water lines and electrical conduits
  - Vertical Placement from top of slab, lid 0 - 6 mm (0" - 1/4") above finished surface
  - Box properly supported on foam (foam below box is set into clear stone for 5" and basement slabs)
  - Box firmly anchored with grout or cement block on box to prevent flotation during pour
  - Conduits installed and capped for electrical (power and thermostats)
  - Conduit installed and capped for optional boiler interlock (optional for electric units for future conversion)
  - Conduits or sleeved water lines installed and capped for water supply and return lines (optional for electric units for future conversion)
  - Box lid handle down, edges taped to box and lid screws in place as per rough in data sheet
- 2) Piping Loops
  - Location and number of elbows as per plan and cutlist (check each loop - extras are noted)
  - Inlets to box connected or capped as per plan
  - Outlets from box connected and insulated or capped as per plan
  - 2 screws installed per joint (4 per fitting) for ALL piping types
  - Insulation installed - 60% on top for half insulation and full insulation, as per plan
- 3) In-slab Services by Others
  - All horizontal hot water lines (including domestic) are thermally isolated from slab by sleeving or insulating, or run in insulation layer, encased in expanding foam
- 4) Comments \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

**PART 3 - FOR ALL SLABS**

I, \_\_\_\_\_, as the person taking responsibility for this installation, certify that the structural portion of the installation was 100% complete when I was personally onsite to inspect it, and that the installation is in accordance with the latest revision of the design drawing, as noted on Page 1.  
 I am an Installer in Training (this report must be counter-signed by the training LSR) or I am a Trained Installer.

Signed: \_\_\_\_\_ Date: \_\_\_\_\_ Phone: \_\_\_\_\_

|  |               |  |        |
|--|---------------|--|--------|
| <b>For Internal Use Only</b>               |               |  |        |
| <input type="checkbox"/> Completed         |               | <input type="checkbox"/> Completed with Deficiencies |        |
| <input type="checkbox"/> Incomplete Report |               |  |        |
| Reviewing Agent                            | Date Received | Authorization Code                                   | Signed |
| Notes/Deficiencies:                        |               |  |        |

# Pre Pour Checklist

## Site Prep

- 3/8"-3/4" clear stone used for top 4"-6" (see drawing) of gravel drainage layer (no fines)

## Edge Element (Does not apply for basements)

- Height of Edge Element above EPS in middle of slab \_\_\_\_\_
- Height of Edge Element above EPS at edge of slab \_\_\_\_\_
- Photographs of installed skirting (minimum 2 photos required)

## Reinforcement

- Continuous top wire mesh as per drawing
- Top and bottom edge strips of wire mesh, tied around pipe with ty-raps, as per drawing
- Wire mesh chaired as per drawing
- Wire mesh and/or rebar under all bearing walls and posts as per drawing
- Top rebar placed and spaced as per drawing
- Concrete cover to be minimum 20 mm (3/4") for top and 30 mm (1-1/4") for bottom

# Pre Pour Checklist

## Heating Box (insert not yet received/installed)

- Type (water or electric) \_\_\_\_\_ Quantity \_\_\_\_\_
- Location as per plan
- Check that box orientation matches plan, noting orientation of water lines and electrical conduits
- Vertical Placement from top of slab, lid 0 - 6 mm (0" - 1/4") above finished surface
- Box firmly anchored with grout or cement block on box to prevent flotation during pour
- Conduits installed and capped for electrical (power and thermostats)
- Conduit installed and capped for optional boiler interlock (optional for electric units for future conversion)
- Box lid handle down, edges taped to box and lid screws in place as per rough in data sheet
- Box properly supported on foam (foam below box is set into clear stone for 5" and basement slabs)
- Conduits or sleeved water lines installed and capped for water supply and return lines (optional for electric)

# Pre Pour Checklist

## Piping Loops

- Location and number of elbows as per plan and cutlist (check each loop - extras are noted)
- Inlets to box connected or capped as per plan
- Outlets from box connected and insulated or capped as per plan
- 2 screws installed per joint (4 per fitting) for ALL piping types
- Insulation installed - 60% on top for half insulation and full insulation, as per plan

## In-slab Services by Others

All horizontal hot water lines (including domestic) are thermally isolated from slab by sleeving or insulating, or run in insulation layer, encased in expanding foam



# Concrete Placement

- Place concrete using a pencil vibrator around areas of congestion, heater boxes and doorway cutouts.
- Concrete must be vibrated to ensure full consolidation.



# Finishing Concrete

- **Leveling the surface with a vibrating screed helps in the consolidation.**



# Post Concrete Placement

- **Keep top of slab moist for 3 days to minimize shrinkage cracking.**
- **This can be done by wetting the slab and tarping or covering with 6 mil poly.**



# Windy Weather

- In windy weather be sure to weigh down the assembled materials beforehand and have the perimeter stone banked up at the



# Pre-Pour Inspection

- A pre-pour inspection is completed by a Legalett licensed inspector



# Dowels/Anchor Bolts

- **Install rebar dowels as per ICF manufacturers' specs around the slab perimeter or 8" anchor bolts for wood framing.**
- **Pre plan to ensure anchor bolts do not line up with stud positioning or door ways.**
- **Alternately, sleeve anchors maybe acceptable**



# LEGALETT



## 4,400 SQ.FT. Single Family Residence

LOCATION : Cornwall, Ontario, Canada  
BUILDER : Teixeira Construction  
DESIGNER : Joshua Teixeira

- 4,400 sq. ft. two-story home with attached 1,450 sq. ft. heated garage was built with the lower 3,600 sq. ft. floor as a LEGALETT Foundation.
- The lower 3,600 sq. ft. floor foundation is divided into five heating zones.
- Room-by-room temperature control is available, and each furnace in the living areas serves areas in the home where the floor is directly heated by the incoming sun in the winter. This allows the free solar heat to be shared throughout the house, transferred from a passively solar heated area to the rest of the floor via the air moving through the LEGALETT System.
- With effective use of passive solar energy, a highly efficient hot water tank, and a very well insulated envelope, this home is heated for less than \$100/ month on average.


*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**

1-866-299-7567  
Sales@L.legalett.ca

# LEGALETT



## Christian Community Centre

**LOCATION** : Thornhill, Ontario  
**BUILDER** : Richard Koekebalcker, Lynwood Construction  
**DESIGNER** : Jan J Wintjes Construction Source

- 6,000 sq.ft. church and community centre

- **Nine heating zones** were used to effectively control the temperature in a wide variety of heat loadings, varying from practically no windows to walls made almost entirely of glazing.
- The use of tile and similar floor coverings means that the parishioners will enjoy **warm feet** during times of reflection in the chapel and community centre, as well as meeting with friends in the open foyer areas.
- The ventilation system can be turned off completely during periods of low or non-occupancy, with **significant cost savings**. Even with the ventilation system off, the church will still be warm and quiet throughout. Energy bills were \$1,600 for the entire 05/06 heating season.

*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**

1-866-299-7567

Sales@Legalett.ca



# Energy Costs

for a 6,400 sq.ft. Assembly Building

| <b>CHRISTIAN COMMUNITY CHURCH , THORNHILL</b> |                       |                         |        |  |
|---|-----------------------|-------------------------|--------|--|
| Enbridge Gas Invoice dates                    | Total amount rendered | Accumulated Gas Charges | GST    | Energy cost  |
| Dec 30'05                                     | 555.36                | 555.36                  | 36.33  | 519.03   |
| Jan 31'06                                     | 579.98                | 1135.34                 | 37.94  | 1061.07  |
| Feb 28'06                                     | 680.36                | 1815.70                 | 44.51  | 1696.92  |
| Mar 30'06                                     | 292.57                | 2108.27                 | 19.14  | 1970.35  |
| Apr 12'06                                     | 582.59                | 2690.86                 | 18.96  | 2533.98 *  |
| May 12'06                                     | 202.57                | 2893.43                 | 13.25  | 2723.3 *   |
| Jun 13'06                                     | 105.61                | 2999.04                 | 6.91   | 2822 *   |
| Jul 13'06                                     | 314.16                | 3313.20                 | 17.76  | 3118.4 *   |
| Aug 14'06                                     | (158.64)              | 3154.56                 | -8.98  | 2968.74 *  |
| Sep 13'06                                     | 127.48                | 3282.04                 | 16.2   | 3080.02 *  |
| Oct 13'06                                     | (67.31)               | 3214.73                 | -3.01  | 3015.72 *  |
| Nov 13'06                                     | 266.60                | 3481.33                 | 18.9   | 3263.42  |
|   | 3,481.33              |                         | 217.91 |  |
|   | (1,896.84)            |                         |        |  |
|   |                       |                         |        | cooking + Dom Hot water 12 mos 2 apartments @ 158.07 per month                                       |
|   |                       |                         |        | Apartments are heated electrically, but allow cooking , showers etc of three persons                 |
|   |                       |                         |        | <b>1,584.49 In-floor heating cost of chapel, offices, Lobby and community room (total 6400 Sqft)</b> |

# LEGALETT



## 5,178 sq.ft. Merrickville Day Nursery School

**LOCATION :** Merrickville, Ontario  
**BUILDER :** Teixeira Construction  
**DESIGNER :** Smith Carter Architects & Engineers Inc.

- **Designed as a sustainable, replicable demonstration project** for other facilities such as nursing homes and health care centers this project features exterior **walls of Insulating Concrete Forms**. State-of-the-art windows minimize heat loss in winter and permit fresh air circulation in summer
- 3 Water Coil Units are used to service **12 Zones**
- Long term benefits:
  - Low energy consumption**
  - Excellent indoor air quality and comfort
  - Low environmental impact

[http://www.merrickville-day-nursery-school.org/new\\_builder\\_news/index.html](http://www.merrickville-day-nursery-school.org/new_builder_news/index.html)

*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**  
1-866-299-7567  
Sales@Legalett.ca

# LEGALETT.



## 1,500 — 2,500 sq.ft. Log Homes

**LOCATION :** The Laurentians, Quebec  
**BUILDER :** SMJ Construction  
**DESIGNER :** Millette-Legare, Architects

- Fiddler Lake Resort is a self-contained **SOLD OUT** development of **80 luxury log homes** 45 minutes North of Montreal.
- Electric Units Servicing 4 zones

For more information on this development visit the web site below  
<http://www.fiddlerlakeresort.com/>

*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**

1-866-299-7567  
Sales@Legalett.ca

# LEGALETT



## Harbour View Café

LOCATION : Brighton, Ontario  
BUILDER : DuCon Construction  
DESIGNER : MOSS SUND Inc.

- A **high water table** mixed with an **old land fill site** found Legalett to be a perfect fit
- Legalett was used **instead of pilings** down to bedrock
- The building had a footprint of only 1200 sq ft. but had 15 corners and **many slab penetrations** required for restaurant and apartment services
- The owners, Jenny Hewitt and Bill Rudland, have commented that they are very impressed with the evenness of the heat in their floors and that it is **costing less than expected** to heat the building
- **2 - 5kW water coil** units were used keeping the cost of providing heat to this project at a minimum

To see more about the resort visit: [www.gosport.ca](http://www.gosport.ca)

*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**  
1-866-259-7567  
Sales@Legalett.ca

# LEGALETT.



## 10,000 sq. ft. Residence

**LOCATION :** Toronto ,Ontario  
**BUILDER :** Fiume and Associates Inc.  
**DESIGNER :** Denis Bowman Architect

- Built in 2000, this 10,000 ft<sup>2</sup> -foundation and 2 floors features 9 water coils and 13 separate heating zones

*"Designed For Comfort, Engineered For Simplicity"*

[www.Legalett.ca](http://www.Legalett.ca)

**LEGALETT**

1-866-259-7567  
Sales@Legalett.ca

Legalett's engineers provide personalised project specific on-line video training for each sold project.

Call Legalett at (866)299-7567 ext 101 to learn more about why we may be the solution you have been looking for.

Thank you for your time and attention